## BRUHAT BANGALORE MAHANAGARA PALIKE

**Name of Work: Modified Estimate For Improvements to roads and drains at Westernside of R K Hegdenagara cross road and surrounding Areas in Ward No.06**

| Sl No | Description of work | Unit | No | Length | Breadth | Depth | Quantity | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|
| | | | | m | m | m | | in Rs | in Rs |
| 1 | KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (P.No-143, I.No-19.1) | | | | | | | | |
| | **For RCC Drain** | Cum | | | | | | | |
| | **Hegdenagar** | | | | | | | | |
| | Medio Pharama Shop Rd | | 2 | 179.30 | 1.20 | 1.10 | 473.35 | | |
| | Cross Rd-1 | | 2 | 59.20 | 1.20 | 1.10 | 156.17 | | |
| | Cross Rd-2 | | 2 | 54.50 | 1.20 | 1.10 | 143.76 | | |
| | 6th Cross Rd | | 2 | 71.20 | 1.00 | 1.10 | 155.49 | | |
| | 3rd Cross Rd | | 2 | 16.00 | 1.00 | 1.10 | 35.09 | | |
| | 4th Cross Rd | | 2 | 18.10 | 1.10 | 1.10 | 43.80 | | |
| | Ex-Man Service Rd | | 2 | 224.50 | 1.20 | 1.10 | 592.41 | | |
| | Cross Rd-3 | | 1 | 93.00 | 1.20 | 1.10 | 122.76 | | |
| | Cross Rd-4 | | 1 | 83.00 | 1.20 | 1.10 | 109.56 | | |
| | Shobitha House Rd | | 1 | 90.00 | 1.20 | 1.10 | 118.80 | | |
| | Cross Rd-5 | | 1 | 17.00 | 1.20 | 1.10 | 22.44 | | |
| | Mother Dairy Rd | | 1 | 51.50 | 1.20 | 1.10 | 67.98 | | |
| | Cross Rd-6 | | 1 | 49.00 | 1.20 | 1.10 | 64.68 | | |
| | Soha Provision Store | | 1 | 41.00 | 1.20 | 1.10 | 54.12 | | |
| | Cross Rd-7 | | 1 | 41.00 | 1.20 | 1.10 | 54.12 | | |
| | **Government School Opp Rd** | | | | | | | | |
| | 4th Cross Rd | | 1 | 190.40 | 1.20 | 1.10 | 251.25 | | |
| | **Culvert** | | | | | | | | |
| | | | 4 | 5.55 | 1.50 | 1.20 | 39.96 | | |
| | | | 5 | 6.45 | 1.80 | 1.20 | 69.56 | | |
| | | | | | | | **2575.31** | | |
| | | | | | Upto 125% | | **2575.31** | 226.02 | **582077.42** |
| | Quoted Rate | 226.02 | | | | | | | |
| 2 | KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222,I No-27.18) | | | | | | | | |
| | **For Drain** | Cum | | | | | | | |
| | **Hegdenagar** | | | | | | | | |
| | Medio Pharama Shop Rd | | 2 | 179.30 | 1.20 | 0.15 | 64.55 | | |
| | Cross Rd-1 | | 2 | 59.20 | 1.20 | 0.15 | 21.31 | | |
| | Cross Rd-2 | | 2 | 54.50 | 1.20 | 0.15 | 19.62 | | |
| | 6th Cross Rd | | 2 | 71.20 | 1.00 | 0.15 | 21.36 | | |
| | 3rd Cross Rd | | 2 | 16.00 | 1.00 | 0.15 | 4.80 | | |
| | 4th Cross Rd | | 2 | 18.10 | 1.10 | 0.15 | 5.97 | | |
| | Ex-Man Service Rd | | 2 | 224.50 | 1.20 | 0.20 | 107.71 | | |
| | Cross Rd-3 | | 1 | 93.00 | 1.20 | 0.15 | 16.74 | | |
| | Cross Rd-4 | | 1 | 83.00 | 1.20 | 0.15 | 14.94 | | |

Scanned by TapScanner

| Sl No | Description of work | Unit | No | Length m | Breadth m | Depth m | Quantity | Rate in Rs | Amount in Rs |
|---|---|---|---|---|---|---|---|---|---|
| | Shobitha House Rd | | 1 | 90.00 | 1.20 | 0.15 | 16.20 | | |
| | Cross Rd-5 | | 1 | 17.00 | 1.20 | 0.15 | 3.06 | | |
| | Mother Dairy Rd | | 1 | 51.50 | 1.20 | 0.15 | 9.27 | | |
| | Cross Rd-6 | | 1 | 49.00 | 1.20 | 0.15 | 8.82 | | |
| | Soha Provision Store | | 1 | 41.00 | 1.20 | 0.15 | 7.38 | | |
| | Cross Rd-7 | | 1 | 41.00 | 1.20 | 0.15 | 7.38 | | |
| | **Government School Opp Rd** | | | | | | | | |
| | 4th Cross Rd | | 1 | 190.40 | 1.20 | 0.15 | 34.22 | | |
| | **Culvert** | | | | | | | | |
| | | | 4 | 5.55 | 1.50 | 0.20 | 6.66 | | |
| | | | 5 | 6.45 | 1.80 | 0.20 | 11.58 | | |
| | **Culvert Ramp** | | 5 | 6.45 | 1.00 | 0.15 | 4.84 | | |
| | **Inside** | | 5 | 6.45 | 1.00 | 0.15 | 4.84 | | |
| | **Outside** | | | | | | **391.25** | 5692.45 | **2227161.31** |
| | | 5692.45 | | | | | | | |
| | Quoted Rate | | | | | | | | |
| | | | | | | | | | |
| 3 | Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and sown size granite metal course aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compcted for walls and bottom including centring shuttering cost of material HOM of machinary curing etc., complete execluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification. (P.No.271, I.No.37.59.2 of PW, P&IWTD S.R 2018-19) | | | | | | | | |
| | **For RCC Drain** | Cum | | | | | | | |
| | **Hegdenagar** | | | | | | | | |
| | **Bottom slab** | | 2 | 179.30 | 1.10 | 0.15 | 59.17 | | |
| | Medio Pharama Shop Rd | | 2 | 59.20 | 1.10 | 0.15 | 19.52 | | |
| | Cross Rd-1 | | 2 | 54.50 | 1.10 | 0.15 | 17.97 | | |
| | Cross Rd-2 | | 2 | 71.20 | 0.90 | 0.15 | 19.22 | | |
| | 6th Cross Rd | | 2 | 16.00 | 0.90 | 0.15 | 4.32 | | |
| | 3rd Cross Rd | | 2 | 18.10 | 1.10 | 0.15 | 5.93 | | |
| | 4th Cross Rd | | 2 | 224.50 | 1.10 | 0.15 | 74.09 | | |
| | Ex-Man Service Rd | | 1 | 93.00 | 1.10 | 0.15 | 15.35 | | |
| | Cross Rd-3 | | 1 | 83.00 | 1.10 | 0.15 | 13.70 | | |
| | Cross Rd-4 | | 1 | 90.00 | 1.10 | 0.15 | 14.85 | | |
| | Shobitha House Rd | | 1 | 17.00 | 1.10 | 0.15 | 2.81 | | |
| | Cross Rd-5 | | 1 | 51.50 | 1.10 | 0.15 | 8.50 | | |
| | Mother Dairy Rd | | 1 | 49.00 | 1.10 | 0.15 | 8.09 | | |
| | Cross Rd-6 | | 1 | 41.00 | 1.10 | 0.15 | 6.77 | | |
| | Soha Provision Store | | 1 | 41.00 | 1.10 | 0.15 | 6.77 | | |
| | Cross Rd-7 | | | | | | | | |
| | **Government School Opp Rd** | | 1 | 190.40 | 1.10 | 0.15 | 31.42 | | |
| | 4th Cross Rd | | | | | | | | |
| | **Side walls** | | 4 | 179.30 | 0.15 | 0.60 | 64.55 | | |
| | Medio Pharama Shop Rd | | 4 | 59.20 | 0.15 | 0.60 | 21.31 | | |
| | Cross Rd-1 | | 4 | 54.50 | 0.15 | 0.60 | 19.62 | | |
| | Cross Rd-2 | | 4 | 71.20 | 0.15 | 0.60 | 25.63 | | |
| | 6th Cross Rd | | 4 | 16.00 | 0.15 | 0.60 | 5.76 | | |
| | 3rd Cross Rd | | 4 | 18.10 | 0.15 | 0.60 | 6.52 | | |
| | 4th Cross Rd | | | | | | | | |

Scanned by TapScanner

| Sl No | Description of work | Unit | No. | Length | Breadth | Depth | Quantity | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|
| | Main Service Rd. | | 4 | [illegible] | 0.45 | 0.60 | [illegible] | | |
| | Cross Rd-1 | | 2 | 41.00 | 0.45 | 0.60 | [illegible] | | |
| | Cross Rd-4 | | 2 | 40.00 | 0.45 | 0.60 | [illegible] | | |
| | Medehha House Rd. | | 2 | 43.00 | 0.45 | 0.60 | [illegible] | | |
| | Cross Rd-5 | | 2 | 41.00 | 0.45 | 0.60 | [illegible] | | |
| | Medhra Dairy Rd. | | 2 | 40.00 | 0.45 | 0.60 | [illegible] | | |
| | Cross Rd-6 | | 2 | 41.00 | 0.45 | 0.60 | [illegible] | | |
| | Soba Provision Store | | 2 | 41.00 | | | | | |
| | Cross Rd-7 | | | | | | | | |
| | Government School Opp Rd. | | 2 | 180.40 | 0.45 | 0.60 | [illegible] | | |
| | 4th Cross Rd. | | | | | | | | |
| | For RCC Culvert | | 4 | 3.50 | 1.80 | 0.30 | 3.78 | | |
| | Raft | | 2 | 0.45 | 1.80 | 0.30 | [illegible] | | |
| | | | | | | | | | |
| | | | 8 | 3.50 | 0.30 | 0.30 | 3.78 | | |
| | side walls | | 16 | 0.45 | 0.30 | 0.45 | 0.90 | | |
| | | | | | | | [illegible] | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | Culvert Ramp | | 2 | 0.45 | 1.15 | 0.10 | 3.74 | | |
| | Inside | | 2 | 0.45 | 1.30 | 0.10 | 3.90 | | |
| | Outside | | | | | | 7.80 | | |
| | | | | | | Net Qty. | [illegible] | | |
| | | | | | | Upto 1.25% | [illegible] | [illegible] | [illegible] |
| | | | | | | | | | |
| | Quoted Rate | [illegible] | | | | | | | |
| 4 | KSRRB - M2300-14: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with annealed wire and anchoring to the adjoining memebrs wherever necessary complete as per design (lens, hooks and wastage shall not be measured and paid) cost of materials, labour, hire of machinery complete as per specifications MORTH Specification No. 1600 & 2400 for TMT bars Fe 500 (Fe No 456, Fe No 415 of PW, P&WTD S.R 2018-19) | | | | | | | | |
| | Considering steel For Drain @ 70kg / cum | Tonne | | 650.15 | 0.070 | | 45.51 | | |
| | Considering steel For Culvert @ 100 kg / cum | | | 30.20 | 0.100 | | 3.02 | | |
| | | | | | | | 48.53 | | |
| | | | | | Upto 1.25% | | 48.53 | [illegible] | [illegible] |
| | Quoted Rate | | | | | | | | |
| 5 | Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M45 using graded granite jelly 20mm and down size with steel reinforcement including form work, lift charges, curing and concrete finished surfaces on both sides etc. complete and as per drawing and the directions of Engineer in charge. (Data Rate) | | | | | | | | |
| | **For drain cover slab** | Sqm | | | | | | | |
| | **Hegdenagar** | | | | | | | | |
| | Medio Pharama Shop Rd | | 2 | 179.30 | 0.90 | | 322.74 | | |
| | Cross Rd-1 | | 2 | 59.20 | 0.90 | | 106.56 | | |
| | Cross Rd-2 | | 2 | 54.50 | 0.90 | | 98.10 | | |

Scanned by TapScanner

| Sl No | Description of work | Unit | No | Length m | Breadth m | Depth m | Quantity | Rate in Rs | Amount in Rs |
|---|---|---|---|---|---|---|---|---|---|
| | 2nd Cross Rd | | 2 | 71.20 | 0.75 | | 106.80 | | |
| | 3rd Cross Rd | | 2 | 16.00 | 0.75 | | 24.00 | | |
| | 4th Cross Rd | | 2 | 18.10 | 0.75 | | 27.15 | | |
| | Ex-Man Service Rd | | 2 | 224.50 | 0.90 | | 404.10 | | |
| | Cross Rd-3 | | 1 | 93.00 | 0.90 | | 83.70 | | |
| | Cross Rd-4 | | 1 | 83.00 | 0.90 | | 74.70 | | |
| | Shobitha House Rd | | 1 | 90.00 | 0.90 | | 81.00 | | |
| | Cross Rd-5 | | 1 | 17.00 | 0.90 | | 15.30 | | |
| | Mother Dairy Rd | | 1 | 51.50 | 0.90 | | 46.35 | | |
| | Cross Rd-6 | | 1 | 49.00 | 0.90 | | 44.10 | | |
| | Soha Provision Store | | 1 | 41.00 | 0.90 | | 36.90 | | |
| | Cross Rd-7 | | 1 | 41.00 | 0.90 | | 37.06 | | |
| | **Government School Opp Rd** | | 1 | 190.40 | 0.90 | | 171.36 | | |
| | 4th Cross Rd | | | | | | | | |
| | **missing/damaged slabs** | | 16 | | 0.90 | | 14.42 | | |
| | | | | | | | **1694.34** | | |
| | | | | | Upto 125% | | **1694.34** | 2453.62 | **4157260.24** |
| | | 2453.62 | | | | | | | |
| | Quoted Rate | | | | | | | | |
| 6 | Providing and Fixing pre cast covering Slab 250mm thick made out of M25 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge. (Data Rate) | | | | | | | | |
| | For Culvert Slabs | Sqm | 4 | 5.55 | 1.20 | | 26.57 | | |
| | | | 5 | 6.45 | 1.50 | | 48.38 | | |
| | | | | | | | **74.95** | | |
| | | | | | Upto 125% | | **74.95** | 5688.36 | **426334.6** |
| | | 5688.36 | | | | | | | |
| | Quoted Rate | | | | | | | | |
| 7 | KSRB 4-1.6 ; Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, I.No.4.6 of PW, P&IWTD SR 2018-19) | | | | | | | | |
| | **For Kerb** | Cum | | | | | | | |
| | **Hegdenagar** | | | | | | | | |
| | Medio Pharama Shop Rd | | 2 | 179.30 | 0.20 | 0.10 | 7.17 | | |
| | Cross Rd-1 | | 2 | 59.20 | 0.20 | 0.10 | 2.37 | | |
| | Cross Rd-2 | | 2 | 54.50 | 0.20 | 0.10 | 2.18 | | |
| | 6th Cross Rd | | 2 | 71.20 | 0.20 | 0.10 | 2.88 | | |
| | Ex-Man Service Rd | | 2 | 178.00 | 0.20 | 0.10 | 7.12 | | |
| | Cross Rd-3 | | 1 | 93.00 | 0.20 | 0.10 | 1.90 | | |
| | Cross Rd-4 | | 1 | 83.00 | 0.20 | 0.10 | 1.69 | | |
| | Shobitha House Rd | | 1 | 90.00 | 0.20 | 0.10 | 1.84 | | |
| | Cross Rd | | 1 | 66.00 | 0.20 | 0.10 | 1.35 | | |
| | Cross Rd-5 | | 1 | 17.00 | 0.20 | 0.10 | 0.35 | | |
| | Mother Dairy Rd | | 1 | 51.00 | 0.20 | 0.10 | 1.04 | | |
| | Cross Rd-6 | | 1 | 49.00 | 0.20 | 0.10 | 1.00 | | |

Scanned by TapScanner

| Sl No | Description of work | Unit | No | Length m | Breadth m | Depth m | Quantity | Rate in Rs | Amount in Rs |
|---|---|---|---|---|---|---|---|---|---|
| | Soha Provision Store | | 1 | 40.00 | 0.20 | 0.10 | 0.82 | | |
| | Cross Rd-7 | | 1 | 41.00 | 0.20 | 0.10 | 0.84 | | |
| | **Government School Opp Rd** | | | | | | | | |
| | 4th Cross Rd | | 1 | 190.40 | 0.20 | 0.10 | 3.88 | | |
| | **Coping** | | 1 | 46.00 | 0.45 | 0.10 | 2.06 | | |
| | | | | | | | **38.46** | | |
| | | | | | Upto 125% | | **38.46** | 6034.11 | **232096.46** |
| | Quoted Rate | 6034.11 | | | | | | | |
| | | | | | | | | | |
| 8 | Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc.,complete. As per the direction of Engineer incharge. (P.No.27, I.No.5.30 of PW, P&IWTD SR 2018-19) | | | | | | | | |
| | **For Kerb** | Nos | | | | | | | |
| | **Hegdenagar** | | | | | | | | |
| | Medio Pharama Shop Rd | | 2 | 179.30 | | | 358.60 | | |
| | Cross Rd-1 | | 2 | 59.20 | | | 118.40 | | |
| | Cross Rd-2 | | 2 | 54.50 | | | 109.00 | | |
| | 6th Cross Rd | | 2 | 71.20 | | | 142.40 | | |
| | Ex-Man Service Rd | | 2 | 178.00 | | | 356.00 | | |
| | Cross Rd-3 | | 1 | 93.00 | | | 93.00 | | |
| | Cross Rd-4 | | 1 | 83.00 | | | 83.00 | | |
| | Shobitha House Rd | | 1 | 90.00 | | | 90.00 | | |
| | Cross Rd | | 1 | 66.00 | | | 66.00 | | |
| | Cross Rd-5 | | 1 | 17.00 | | | 17.00 | | |
| | Mother Dairy Rd | | 1 | 51.00 | | | 51.00 | | |
| | Cross Rd-6 | | 1 | 49.00 | | | 49.00 | | |
| | Soha Provision Store | | 1 | 40.00 | | | 40.00 | | |
| | Cross Rd-7 | | 1 | 41.00 | | | 41.00 | | |
| | **Government School Opp Rd** | | | | | | | | |
| | 4th Cross Rd | | 1 | 190.40 | | | 190.40 | | |
| | | | | | | | 1804.80 | | |
| | | | | | | | **4011.00** | | |
| | | | | | Upto 125% | | **3980.00** | 454.06 | **1807158.80** |
| | | | | | Above 125% | | **31.00** | 454.06 | **14075.86** |
| | Quoted Rate | 454.06 | | | | | | | |
| | | | | | | | | | |
| 9 | Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 Specification No. KSRRB M800-6. (P.No.180, I.No.24.1 of PW, P&IWTD SR 2018-19) | | | | | | | | |
| | **For Kerb** | Sqm | | | | | | | |
| | **Hegdenagar** | | | | | | | | |
| | Medio Pharama Shop Rd | | 2 | 179.30 | 0.40 | | 143.44 | | |
| | Cross Rd-1 | | 2 | 59.20 | 0.40 | | 47.36 | | |
| | Cross Rd-2 | | 2 | 54.50 | 0.40 | | 43.60 | | |
| | 6th Cross Rd | | 2 | 71.20 | 0.40 | | 56.96 | | |
| | Ex-Man Service Rd | | 2 | 178.00 | 0.40 | | 142.40 | | |
| | Cross Rd-3 | | 1 | 93.00 | 0.40 | | 37.20 | | |
| | Cross Rd-4 | | 1 | 83.00 | 0.40 | | 33.20 | | |
| | Shobitha House Rd | | 1 | 90.00 | 0.40 | | 36.00 | | |
| | Cross Rd | | 1 | 66.00 | 0.40 | | 26.40 | | |

Scanned by TapScanner

| Sl No | Description of work | Unit | No | Length m | Breadth m | Depth m | Quantity | Rate in Rs | Amount in Rs |
|---|---|---|---|---|---|---|---|---|---|
| | oss Rd-5 | | 1 | 17.00 | 0.40 | | 6.80 | | |
| | Mother Dairy Rd | | 1 | 51.00 | 0.40 | | 20.40 | | |
| | Cross Rd-6 | | 1 | 49.00 | 0.40 | | 19.60 | | |
| | Soha Provision Store | | 1 | 40.00 | 0.40 | | 16.00 | | |
| | Cross Rd-7 | | 1 | 41.00 | 0.40 | | 16.36 | | |
| | **Government School Opp Rd** | | | | | | | | |
| | 4th Cross Rd | | 1 | 190.40 | 0.40 | | 76.16 | | |
| | | | | | | | **721.88** | | |
| | | | | | Upto 125% | | **620.50** | 89.03 | **55244.06** |
| | | | | | Above 125% | | **101.38** | 89.03 | **9026.29** |
| | Quoted Rate | 89.03 | | | | | | | |
| 10 | KSRRB M200-24. Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperately complete | | | | | | | | |
| | | | | | | | **0.00** | 1021.99 | **0.00** |
| 11 | Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on | | | | | | | | |
| | | | | | | | **0.00** | 2094.47 | **0.00** |
| 12 | Constructing un-reinforced, plain cement concrete for pavements using Grade concrete M30 over a prepared base with OPC coarse aggregate at 0.69 cum, fine aggregates at 0.46 cum,Coarse and fine aggregate conforming to IS:383-2016, with Superplastizer at 3 lts conforming to IS 9103-2008. mixed in | | | | | | | | |
| | | | | | | | **0.00** | 5470.99 | **0.00** |
| | | | | | | | | Sub Total 1 Rs. | **18367991.56** |
| | Miscellaneous & Rounding off | | | | | | | | 8494.99 |
| | | | | | | | | Total Rs. | **18376486.55** |

Technical Sanction
Accorded for .....
Head of A.C. .....
CER NO :..... Dt:..

CE

Assistant Engineer
Project Division Yelahanka
BBMP
15/9/2024

Assistant Executive Engineer
Project Division Yelahanka
BBMP

Asst. Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore - 92

Executive Engineer
Project Division Yelahanka
BBMP

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Executive Engineer Project Division Yelahanka Zone

Scanned by TapScanner